



CITY OF SAN ANTONIO

July 7, 2005

Mr. Christopher Sims

M.W. Cude Engineers
10325 Bandera Road
San Antonio, TX 78250

Re: Park Place Phase II (Amendment)

MDP # 748A

Dear Mr. Christopher Sims:

The City Staff Development Review Committee has reviewed Park Place Phase II Master Development Plan amendment, M.D.P. # 748A. Please find enclosed a signed copy for your files. Your plan was accepted, however please note the following:

- In consideration of public safety and convenience, excessive grades by reason of topography should be avoided in street layouts and arrangements.
- Any access and R.O.W. issues along state facilities will need to be resolved with the Texas Department of Transportation (TXDOT). For information about these requirements you can contact TXDOT at 615-5814.
- This development will need to comply with tree preservation ordinance #85262. For information about these requirements you can contact Tree Preservation at 207-1111.
- It will be expected that you will plat all of the property depicted in your Master Development Plan (M.D.P) to include floodplains, drainage areas and open space.

- Development Services, TIA Engineering Section has indicated as part of their conditional approval, improvements along the project limits are necessary and shall be provided by the developer, on and before the completion of the Park Place II Development, at no cost to the City of San Antonio:
 1. Construction of an internal collector street (Rousseau Road extension) approximately 3,140 feet in length. The collector shall consist of 70 -feet of ROW and 44- feet of pavement.
 2. At the internal collector street (Rousseau Road extension) intersection at Marbach Road, the developer shall design and construct a westbound right-turn lane on Marbach Road (200 feet in length) when this intersection is constructed..
 3. At the internal collector street (Rousseau Road extension) intersection at Marbach Road, the developer shall dedicate ROW (200-feet in length) to provide a southbound right-turn lane on the internal collector street (Rousseau Road extension) when this intersection is constructed.
 4. The internal collector bridge (all weather crossing) over Medio Creek Tributary, which provides additional access to Park Place II, is required and must be in place prior to completion of the Unit and or Phase adjacent to Medio Creek Tributary.
 5. The Local A bridge (all weather crossing) over Medio Creek Tributary shall be designed and constructed under the Phase 5 and or Unit 5. This all weather crossing is a east – west stub out adjacent to the northwest side of the proposed development as shown on the approved Master Development Plan.
 6. The additional direct access point from Manor Creek Road (connecting Park Place to Rousseau Road extension) shall be connected once the area west of Park Place and Park Place II is constructed.

Mr. Christopher Sims

Page 3

July 7, 2005


- I would encourage you to work closely with the school district, so that they can plan accordingly.

Please note that this action by the committee does not establish any commitment for the provision of utilities, services or zoning of any type now or in the future by the City of San Antonio. If the proposed development is not platted in phases this Master Development Plan (M.D.P.) will be invalid.

All Platting shall comply with the Unified Development Code, Master Plan and Major Thoroughfare Plan for the city of San Antonio.


If you have any questions regarding this matter, please contact Mr. Michael O. Herrera, at (210) 207-7873.

Sincerely,



Roderick J. Sanchez, A.I.C.P.
Assistant Director, Development Services


cc: Sam Dent, P. E., Development Services
Richard Chamberlin, P.E., Development Services
Arturo Villarreal Jr, P.E. Strom Water Engineering



LOCATION MAP N.T.S.


CURVE	DELTA	RADIUS	LENGTH	TANGENT
C1	31°16'16"	386.19'	210.78'	108.08'

LINE	BEARING	LENGTH
L1	S00°14'48"W	258.57'
L2	S15°45'38"W	236.38'
L3	N18°59'28"W	195.12'
L4	N40°07'55"W	136.60'
L5	N54°53'22"W	74.97'
L6	N81°56'31"W	125.37'
L7	N69°20'15"W	111.22'
L8	S85°04'33"E	218.30'
L9	N01°26'43"E	330.88'
L10	N13°47'53"W	176.21'
L11	N28°50'54"E	255.96'
L12	N54°50'28"E	402.88'
L13	S89°49'37"E	131.83'




TYPICAL LOT SITE PLAN

LAREDO CONCORD, LTD.
185.50 ACRES
VOL. 11283 PG. 520



LEGEND:
 ——— MDP LIMITS
 - - - - - PHASE LIMITS



OWNER & DEVELOPER
 ARMADILLO CONSTRUCTION CO., LTD.
 14026 NORTHBROOK
 SAN ANTONIO, TEXAS 78232
 CONTACT PERSON: ARTHUR ZUNIGA
 PHONE: (210) 662-0066
 FAX: (210) 666-8787

CIVIL ENGINEER
 M.W. CUDE ENGINEERS, L.L.C.
 CONTACT PERSON: JOSHUA CUDE, E.I.T.
 10325 BANDERA ROAD
 SAN ANTONIO, TEXAS 78250
 (210) 681-2951
 FAX: (210) 523-7112
 WWW.MWCUDE.COM
 INFO@MWCUDE.COM

PLAN HAS BEEN ACCEPTED BY
 COS [Signature]
 7/6/05 748A
 (date) (number)
 If no plate are filed, plan will expire
 On 1/5/07
 1st plat filed on _____


LEGAL DESCRIPTION
 213.9 ACRE TRACT OF LAND OUT OF THE ANTONIO FUENTES SURVEY, NO. 358, ABSTRACT NO. 248, COUNTY BLOCK 4333 AND THE WILLIAM T. NEIL SURVEY NO. 62, ABSTRACT NO. 544, COUNTY BLOCK 5197, BEXAR COUNTY, TEXAS AND ALSO BEING THE 213.9 ACRE TRACT AS DESCRIBED IN A DEED RECORDED IN VOLUME 10199, PAGE 345 OF THE OFFICIAL PUBLIC RECORDS OF REAL PROPERTY, BEXAR COUNTY, TEXAS

- NOTE:**
- CUL-DE-SAC STREETS LONGER THAN 500 L.F. SHALL ADHERE TO THE CSA U.D.C. MINIMUM 30' PAVEMENT REQUIREMENT.
 - ORIGIN OF STATE PLANE COORDINATES: NGS MARK MILLER PID AY0121
 - THE PROPERTY IS OUTSIDE THE CITY LIMITS OF THE CITY OF SAN ANTONIO.
 - THE PROPERTY IS NOT WITHIN THE EDWARDS AQUIFER RECHARGE ZONE.
 - SEWER SERVICE WILL BE PROVIDED BY SAN ANTONIO WATER SYSTEM.
 - WATER SERVICE WILL BE PROVIDED BY BEXAR METROPOLITAN WATER DISTRICT.
 - THE FRONT, SIDE, AND REAR SETBACKS WILL CONFORM TO THE MINIMUM SETBACKS AS WRITTEN IN THE UNIFIED DEVELOPMENT CODE.
 - A VARIABLE SIGHT DISTANCE CLEARANCE EASEMENT WILL BE REQUIRED AT CORNER LOTS IF THE INTERSECTION DOES NOT MEET SIGHT DISTANCE REQUIREMENTS AS DEFINED IN AASHTO MANUAL, 2001 EDITION.
 - ALL STREETS SHOWN HEREIN ARE 50' R.O.W. PUBLIC STREETS, UNLESS OTHERWISE INDICATED.
 - NORTHSIDE & SOUTHWEST INDEPENDENT SCHOOL DISTRICT.
 - NO RESIDENTIAL DRIVEWAY ACCESS IS PERMITTED TO COLLECTOR STREET.
 - COLLECTOR STREET WILL BE PLATTED AND CONSTRUCTED TO THE WEST OF MASTER DEVELOPMENT PLAN WITH UNIT 6.
 - THE APPROXIMATE LIMITS OF THE MEDIO CREEK FLOODPLAIN ARE SHOWN ON THIS MAP ARE BASED UPON A STUDY BY VICKERY & ASSOCIATES, INC. DATED JANUARY 28, 2003. A DETAIL STUDY WILL BE PROVIDED WITH UNIT 6.
 - A 4' WIDE SIDEWALK TO BE PROVIDED FOR PEDESTRIAN ACCESS, ON ALL PROPOSED ROADWAYS.

ITEM	ACRES	# UNITS	DU./AC.	PHASING SEQUENCE
UNIT 1	23.48	74	3.15	11
UNIT 1A	2.01	7	3.48	11
UNIT 1B	3.54	1	0.28	4
UNIT 2	23.26	116	4.99	2
UNIT 3	11.55	69	5.97	5
UNIT 4	13.03	62	4.76	7
UNIT 5	14.65	62	4.23	3
UNIT 6	23.07	117	5.07	10
UNIT 7	14.33	69	4.82	6
UNIT 8	11.55	52	4.50	8
UNIT 9	9.09	60	6.60	9
OTHER SPACE	64.34	0	0	-
TOTAL DEVELOPMENT	213.90	688	3.22	-

PARK AND OPEN SPACE REQUIREMENTS:	
1 ACRE PER 114 LOTS	6.19 ACRES
TOTAL OPEN SPACE PROVIDED	11.51 ACRES
1. PICNIC AREA / OPEN SPACE	2.69 ACRES
2. GRASS AREA / PARK AREA	3.54 ACRES
3. PICNIC AREA / OPEN SPACE	0.51 ACRES
4. GREENWAY / GREENBELT	4.77 ACRES

AMENDMENTS
 A. REVISIONS INCLUDE LOCAL A STREET CONFIGURATION, LOT DEPTH, LOT DENSITY REDUCTION, & IS CLASSIFIED AS A MINOR AMENDMENT PER THE CITY OF SAN ANTONIO UNIFIED DEVELOPMENT CODE SECTION 35-412(G)(2)



TYPICAL LOCAL "A" STREET CROSS-SECTION

200' ELECTRIC ESM'T
 VOL. 5709, PG. 455
 VOL. 5773, PG. 839

PARK PLACE PHASE II SUBDIVISION
 MASTER DEVELOPMENT PLAN #748A
 MARCH 2005

M.W. CUDE ENGINEERS, L.L.C.
 CIVIL ENGINEERS & SURVEYORS
 WWW.MWCUDE.COM

10325 BANDERA ROAD
 SAN ANTONIO, TEXAS 78250
 TEL: 210.681.2951
 FAX: 210.523.7112

REVISIONS:
 1. 6/29/05 MDP REV.
 2.
 3.
 4.
 5.
 6.

DATE: 03/21/05 PROJECT NO: 214805
 DRAWN BY: I.J.C./J.L.R. CHECKED BY: I.J.C.

SHEET 1 OF 1