

TYPICAL SECTION 50' ROADWAY

(RESIDENTIAL P.U.D. STREET)
NOT TO SCALE



TYPICAL SECTION 60' ROADWAY

(RESIDENTIAL P.U.D. STREET)
NOT TO SCALE



LOCATION MAP

TABLE B AREA COMPUTAIONS AND RATIOS	UNIT 1A AREA (AC)	UNIT 1B AREA (AC)	UNIT 1C AREA (AC)	UNIT 1D AREA (AC)	UNIT 2A AREA (AC)	UNIT 2B AREA (AC)	UNIT 2C AREA (AC)	UNIT 3A AREA (AC)	UNIT 3B AREA (AC)	UNIT 3C AREA (AC)	TOTAL AREA (AC)
1. GROSS SITE AREA	24.57	21.24	21.91	16.84	11.9	25.84	19.44	19.39	26.90	11.79	199.82
LESS											
A. TOTAL STREET RIGHT OF WAY	5.08	4.15	2.90	3.06	2.9	3.23	2.19	3.7	4.4	1.87	32.51
B. TOTAL DRIVEWAYS (DRIVEWAYS @ 20'x20' EACH LOT)	0.70	0.48	0.32	0.57	0.40	0.49	0.19	0.24	0.45	0.28	4.43
C. TOTAL STRUCTURE COVERAGE (HOMES @ 2500 SF EACH LOT)	4.36	2.98	2.01	3.56	2.13	2.53	1.21	4.09	1.81	1.72	27.73
2. TOTAL OPEN SPACE	14.43	13.63	16.68	9.65	7.70	19.68	15.86	11.02	19.50	7.92	135.15
3. OPEN SPACE RATIO	58.7%	64.2%	76.1%	57.3%	0.57%	76.2%	81.6 %	56.8 %	72.5 %	67.2%	67.6%

(LDB) SINGLE FAMILY PUD

TABLE C DENSITY TABLE	UNIT 1A	UNIT 1B	UNIT 1C	UNIT 1D	UNIT 2A	UNIT 2B	UNIT 2C	UNIT 3A	UNIT 3B	UNIT 3C	TOTAL
AREA OF PUD (AC)	24.57	21.24	21.91	16.84	11.90	25.84	19.44	19.39	26.90	11.79	199.82
DWELLING UNITS (EA)	74	49	59	62	44	44	24	70	49	30	472
DENSITY (UNITS/ ACRE)	3.0	2.3	1.3	3.7	3.7	1.7	1.1	3.6	1.8	2.5	2.4

CLEAR VISION CALCULATIONS

TYPICAL 30' X 30' INTERSECTION. NOTE 1

TWO WAY - EQUATION D R1 = 0.65x(ISD2) - (W1/2 + KD)

ISD2:	300 LF
W1:	30 LF
KD:	2
R1:	178 LF

TWO WAY - EQUATION A L1 = 13x(ISD1)/(13 + (W1/2) + KA) - 4

ISD1:	300 LF
W1:	30 LF
KA:	7
L1:	107 LF

CURB LENGTH= R1

CURB LENGTH= L1

CLEAR VISION CALCULATIONS

TYPICAL 40' X 30' INTERSECTION (W1 = 40') NOTE 3

TWO WAY - EQUATION D R1 = 0.65x(ISD2) - (W1/2 + KD)

ISD2:	300 LF
W1:	40 LF
KD:	2
R1:	173 LF

CURB LENGTH= R1

TWO WAY - EQUATION A L1 = 13x(ISD1)/(13 + (W1/2) + KA) - 4

ISD1:	300 LF
W1:	40 LF
KA:	7
L1:	94 LF

CURB LENGTH= L1

TYPICAL 44' X 30' INTERSECTION (W1 = 30')

TWO WAY - EQUATION D R1 = 0.65x(ISD2) - (W1/2 + KD)

ISD2:	300 LF
W1:	30 LF
KD:	2
R1:	176 LF

TWO WAY - EQUATION A L1 = 13x(ISD1)/(13 + (W1/2) + KA) - 4

ISD1:	300 LF
W1:	30 LF
KA:	7
L1:	107 LF

CLEAR VISION CALCULATIONS

TYPICAL 40' X 62' INTERSECTION (W1 = 40') NOTE 2

TWO WAY - EQUATION D R1 = 0.65x(ISD2) - (W1/2 + KD)

ISD2:	500 LF
W1:	40 LF
KD:	2
R1:	303 LF

TWO WAY - EQUATION A L1 = 13x(ISD1)/(13 + (W1/2) + KA) - 4

ISD1:	300 LF
W1:	40 LF
KA:	7
L1:	94 LF

TYPICAL 40' X 62' INTERSECTION (W1 = 62')

TWO WAY - EQUATION D R1 = 0.65x(ISD2) - (W1/2 + KD)

ISD2:	300 LF
W1:	62 LF
KD:	-5
R1:	169 LF

CURB LENGTH= R1

TWO WAY - EQUATION A L1 = 13x(ISD1)/(13 + (W1/2) + KA) - 4

ISD1:	500 LF
W1:	62 LF
KA:	0
L1:	144 LF

CURB LENGTH= L1

CLEAR VISION CALCULATIONS

TYPICAL 40' X 40' INTERSECTION NOTE 4

TWO WAY - EQUATION D R1 = 0.65x(ISD2) - (W1/2 + KD)

ISD2:	300 LF
W1:	40 LF
KD:	2
R1:	173 LF

CURB LENGTH= R1

TWO WAY - EQUATION A L1 = 13x(ISD1)/(13 + (W1/2) + KA) - 4

ISD1:	300 LF
W1:	40 LF
KA:	7
L1:	94 LF

CURB LENGTH= L1

CLEAR VISION INTERSECTIONS

UNIT		INTERSECTION	W1 (LF)	W2 (LF)
UNIT 1	UNIT 1A	U1A1	40	62
		U1A2	40	40
		U1A3	30	30
		U1A4	30	30
		U1A5	30	30
		U1A6	30	30
		U1A7	30	30
		U1A8	30	30
		U1A9	30	30
	UNIT 1B	U1B1	40	62
		U1B2	40	40
		U1B3	40	40
		U1B4	30	40
		U1B5	30	30
	UNIT 1C	U1C1	40	62
		U1C2	40	40
		U1C3	30	30
UNIT 2	UNIT 2A	U2A1	40	30
	UNIT 2B	U2B1	30	40
	UNIT 2C	U2C1	30	30
		U2C2	30	30
UNIT 3	UNIT 3A	U3A1	40	30
		U3A2	30	30
	UNIT 3B	U3B1	30	30
		U3B2	30	30
		U3B3	30	30
	UNIT 3C	U3C1	30	62
		U3C2	30	30
		U3C3	30	30

CLEAR VISION CALCULATIONS

TYPICAL 30' X 62' INTERSECTION (W1 = 30') NOTE 5

TWO WAY - EQUATION D R1 = 0.65x(ISD2) - (W1/2 + KD)

ISD2:	500 LF
W1:	30 LF
KD:	2
R1:	308 LF

CURB LENGTH= R1

TWO WAY - EQUATION A L1 = 13x(ISD1)/(13 + (W1/2) + KA) - 4

ISD1:	300 LF
W1:	30 LF
KA:	7
L1:	108 LF

CURB LENGTH= L1

TYPICAL 62' X 30' INTERSECTION (W1 = 62')

TWO WAY - EQUATION D R1 = 0.65x(ISD2) - (W1/2 + KD)

ISD2:	300 LF
W1:	62 LF
KD:	-5
R1:	169 LF

CURB LENGTH= R1

TWO WAY - EQUATION A L1 = 13x(ISD1)/(13 + (W1/2) + KA) - 4

ISD1:	500 LF
W1:	62 LF
KA:	0
L1:	144 LF

CURB LENGTH= L1

FOR INTERSECTIONS WHERE BOTH STREETS ARE 30' WIDE, USE NOTE 1. FOR INTERSECTIONS WHERE 40' WIDE STREET INTERSECTS 62' WIDE STREET USE NOTE 2. FOR INTERSECTIONS WHERE 44' WIDE STREET INTERSECTS 30' WIDE STREET USE NOTE 3. FOR INTERSECTIONS WHERE 40' WIDE STREET INTERSECTS 40' WIDE STREET USE NOTE 4. FOR STREETS WHERE 30' WIDE STREET INTERSECTS 62' WIDE STREET USE NOTE 5.

NOTE: ALL STREETS ARE 30' WIDE, EXCEPT WHERE OTHERWISE NOTED.

TABLE A YARD REQUIREMENTS AND SIDEWALKS	DISTANCE
1. FRONT YARD SETBACK ALL LOTS	25'
2. SIDEYARD SETBACKS	
A. INTERIOR LOT LINES	5'
B. CORNER LOT LINE ABUTTING STREET	15'
3. REAR YARD SETBACK ALL LOTS	25'
4. 5' SIDEWALK REQUIRED ON ALL FRONT AND SIDE YARDS ABUTTING PUBLIC OR PRIVATE STREETS.	

	UNIT 1A	UNIT 1B	UNIT 1C
GATE DETAIL	2	2	2
# OF GATES	ARM	ARM	ARU
TYPE OF GATE	120	120	120
MAX. CAPACITY CARS/HR.	MANNED	MANNED	MANNED
MANNED/MECHANICAL	20'	25'	25'
TURN AROUND RADIUS	2	2	2
# OF LANES INTO UNIT	11'	11'	11'
LANE WIDTH	2	2	2
# CARS/ LANE			

BIG SPRINGS, PUD AMENDMENT TO PUD PLAN 95-018

THIS AMENDMENT IS PREPARED BY PAPE DAWSON ENGINEERS, INC. AS AUTHORIZED BY THE SITTERLE CORPORATION TO REFLECT NEW LAYOUTS FOR UNITS 1D, 2B, AND 2C. CHANGES FOR REPLATS IN UNITS 1A, 1B, AND 1C. FOR REVISING UNIT DESIGNATIONS FOR 3A, 3B, AND 3C INCLUDING OTHER MINOR LOT VARIATIONS WITHIN THE PROJECT

PAPE-DAWSON ENGINEERS
CIVIL & ENVIRONMENTAL
SAN ANTONIO TEXAS 78216
555 E. RAMSEY 210-375-9000

DIRECTOR OF PLANNING: _____



GRAPHIC SCALE

(IN FEET)
1 inch = 200 ft.



TYPICAL CLEAR VISION INTERSECTION LAYOUT (NOT TO SCALE)

STREET 1 IS LOCATION OF CAR IN RIGHT LANE

PUD LEGEND

U2A	INTERSECTION LABEL
	UNIT BOUNDARY
	200' AREA OF NOTIFICATION
	PUD BOUNDARY
04833000000	PROPERTY TAX ID NUMBER
CB4833	CB/NCB NUMBER
P-3A	PARCEL NUMBER

APPROVED
PLANNED UNIT DEVELOPMENT
Planning Commission
City of San Antonio
Chairman/Secretary Date: 1-11-95

RECEIVED
SEP 12 PM 2:47
SAN ANTONIO PLANNING DEPARTMENT

Director of Planning Date: 1-11-95

REVISIONS			
1	DEC. 94	CLARIFICATION ADDED TO NOTES	CRH
2	8/25/95	CHECKLIST (SEE NOTES 3, 5)	CRH
3	9/95	PLOTTED UNIT 2D + 2C	KDK
NO.	DATE	REVISION	BY

JOB No. 3813.10

DATE: APR., 1994
DESIGNED BY: S.D.A.
DRAWN BY: S.D.A.
CHECKED BY: C.R.H.
SCALE: 1" = 200'
FILE NAME: 93711PUD.DWG
SUPPORT: PC93711

HALLENBERGER ENGINEERING
ENGINEERS
PLANNERS
SURVEYORS
11322 SIR WINSTON (210) 549-6571
SAN ANTONIO, TEXAS 78216

BIG SPRINGS DEVELOPMENT P.U.D.

MASTER PLAN

1699 BY BIG SPRING LIMITED

PUD PLAN

PUD SHEET

SHEET ___ OF ___

#95-018